



May 20, 2021

**Contract 2021-06  
ALERT NEW LONDON PIER REHABILITATION  
Addendum No. 03**

**Delete Item 519E11100 Patching Concrete Surfaces, 4 SF;**

**Delete Item 51143221 Class QC SCC Concrete, Pier, As Per Plan, 23CY;**

Concrete for the pier encasement is still required to be Class QC SCC Concrete, Pier, As Per Plan. Concrete for pile encasement is paid for under Item 507E21200 Special – Pile Encasement.

**Delete Item 530E99100A Special – Structures Misc.: Pier Encasement Mockup, 1 Ea.**

**Change Item 601E32000 Rock Channel Protection, Type A with Filter, 177CY;**

Rock channel protection quantity is reduced to 177CY from 243CY by removing the Type A rock up the slope. The proposed RCP around each pier shall remain.

**Plan Changes**

1. One optional construction joint per pier column is permitted
2. The depth of the dowl holes into the pier cap shall be a minimum of 6-3/4".
3. The requirement of Proposal Note "**Special: General and Sub Contractor Qualifications**" is waived for Items 514E00050 Surface Preparation of Existing Structural Steel and Item 514E00056 Field Painting of Existing Structural Steel, Prime Coat.

**Updated Engineer's Estimate = \$284,339.00**

*Attached Revised "Schedule of Prices"*

**Please e-mail or call our office when you have received this Addendum.**

**taylor@mceo.org**

**Melissa Taylor; 513-785-4115**

ADDENDUM #3						
ALERT NEW LONDON ROAD PIER REHABILITATION						
Contract 2021-06 - Schedule of Prices						
Report Date: 5/20/2021						
Line	Number	Description	Unit	Contract Quantity	Unit Price	Total
<b>EROSION CONTROL</b>						
3	601E32000	ROCK CHANNEL PROTECTION, TYPE A WITH FILTER	CY	177		
6	832E15000	STORM WATER POLLUTION PREVENTION PLAN This item includes all costs associated with the development, implementation, inspection and the required documentation of a Storm Water Pollution Prevention Plan for the Project described in this Contract. all of the specifications and requirements of ODOT supplemental specification 832 shall apply.	LS	1		
5	832E30000	EROSION CONTROL This item is for the installation of Storm Water BMPS as defined in appendix "F" of ODOT supplemental specifications 832. The Contractor shall enter \$1.00 in the unit price column and \$6,000.00 in the total column. If the Contractor neglects to enter the correct figure(s) the Contractors bid will be corrected and the process for "Mistake In Bid" shall follow. No work will be recognized or paid under this item unless agreed upon and approved by an authorized representative of the Butler County Engineer's Office.	EACH	6,000		
				<b>TOTAL: EROSION CONTROL</b>		
<b>INCIDENTALS</b>						
20	614E11000	MAINTAINING TRAFFIC	LS	1		
21	623E10000	CONSTRUCTION LAYOUT STAKES AND SURVEYING	LS	1		
22	624E10000	MOBILIZATION	LS	1		
23	802E00001	PREMIUM ON INDUSTRIAL INSURANCE	LS	1		
24	802E00002	PREMIUM ON BID BOND	LS	1		
25	802E00003	CONTINGENCIES The Contractor shall enter \$1.00 in the unit price column and \$20,000.00 in the total column. If the Contractor neglects to enter the correct figure(s), the Contractor's bid will be corrected and the process for "Mistake in Bid" shall follow. This item will be used in the event that there are change orders in the Contract. No work will be paid or recognized under this item unless agreed upon in writing by an authorized representative of the Butler County Engineer's Office.	EA	20,000		
				<b>TOTAL: INCIDENTALS</b>		
<b>ROADWAY</b>						
1	201E11000	CLEARING AND GRUBBING	LS	1		
2	SPEC6590015	SITE RESTORATION	LS	1		
				<b>TOTAL: ROADWAY</b>		
<b>STRUCTURE REPAIR (BUT-CR222-02.8581)</b>						
7	202E11203	PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	LS	1		
8	503E11101	COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN	LS	1		
9	503E21300	UNCLASSIFIED EXCAVATION	LS	1		
10	507E71200	SPECIAL - PILE ENCASEMENT	FT	156		
11	509E10001	EPOXY COATED REINFORCING STEEL, AS PER PLAN	LB	3,902		
12	510E10001	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS PER PLAN	EACH	68		
14	512E10100	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	SY	200		
15	513E20000	WELDED STUD SHEAR CONNECTORS	EACH	300		

ADDENDUM #3						
ALERT NEW LONDON ROAD PIER REHABILITATION						
Contract 2021-06 - Schedule of Prices						
Report Date: 5/20/2021						
Line	Number	Description	Unit	Contract Quantity	Unit Price	Total
16	514E00050	SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	SF	907		
17	514E00056	FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME COAT	SF	907		
19	530E99100	SPECIAL - STRUCTURES MISC.: Temporary Construction Site Access	LUMP	1		
				<b>TOTAL: STRUCTURE REPAIR (BUT-CR222-02.8581)</b>		
						<b>TOTAL BID:</b>