



March 16, 2022

**Contract 2022-03
Butler Warren Road At Princeton Road Improvements
Addendum No. 01**

Delete Item: 441E50200 ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), 700 CY.

Add Item: 441E50300 ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448), 700 CY.

Add Proposal Note: The following conduits shall be 707.33 Corrugated Polyethylene Smooth Lined Pipe:

Line #37 BC811046001, 12" Conduit, Type C

Line #38 BC811E07400, 18" Conduit, Type B

Line #41 BC811E044001, 12" Conduit Type B

Attached Revised "Schedule Of Prices"

**Please e-mail or call our office when you have received this Addendum.
taylor@m@bceo.org
Melissa Taylor; 513-785-4115**

ADDENDUM #1						
WAR-CR2-06.40, BUTLER WARREN AT PRINCETON ROAD IMPROVEMENTS						
Contract 2022-03 - Schedule of Prices						
Report Date: 03/16/2022						
Line	Number	Description	Unit	Quantity	Unit Price	Total
01-ROADWAY						
1	201E11000	CLEARING AND GRUBBING	LS	1		
2	202E20010	HEADWALL REMOVED	EACH	2		
3	202E23000	PAVEMENT REMOVED	SY	5,609		
4	202E58100	CATCH BASIN REMOVED	EACH	3		
5	202E32000	CURB REMOVED	FT	328		
6	202E35100	PIPE REMOVED, 24" AND UNDER	FT	355		
7	203E10000	EXCAVATION	CY	5,636		
8	203E20000	EMBANKMENT	CY	5,330		
12	204E10000	SUBGRADE COMPACTION	SY	10,850		
13	204E45000	PROOF ROLLING	HOUR	6		
101	802E60303A	SUBGRADE REPAIR, AS PER PLAN	CY	1,200		
					TOTAL: ROADWAY	
02-EROSION CONTROL						
15	601E21050	TIED CONCRETE BLOCK MAT, TYPE 1 Underlayment	SY	5.3		
16	601E32200	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	CY	3.33		
17	659E00100	SOIL ANALYSIS TEST	EACH	1		
18	659E00300	TOPSOIL 4"	CY	1,577		
19	659E10001	SEEDING AND MULCHING, AS PER PLAN	SY	14,213		
20	659E14000	REPAIR SEEDING AND MULCHING	SY	710		
21	659E20000	COMMERCIAL FERTILIZER	TON	2		
22	659E31000	LIME	ACRE	3		
23	659E35000	WATER	MGAL	38		
24	832E15000	STORM WATER POLLUTION PREVENTION PLAN This item includes all costs associated with the development, implementation, inspection and the required documentation of a Storm Water Pollution Prevention Plan for the Project described in this Contract. all of the specifications and requirements of ODOT supplemental specification 832 shall apply.	LS	1		
25	832E15002	STORM WATER POLLUTION PREVENTION INSPECTIONS	LS	1		
26	832E15010	STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE	LS	1		
27	832E30000	EROSION CONTROL This item is for the installation of Storm Water BMPS as defined in appendix "F" of ODOT supplemental specifications 832. The Contractor shall enter \$1.00 in the unit price column and \$20,000.00 in the total column. If the Contractor neglects to enter the correct figure(s) the Contractors bid will be corrected and the process for "Mistake In Bid" shall follow. No work will be recognized or paid under this item unless agreed upon and approved by an authorized representative of the Butler County Engineer's Office.	EACH	20,000		

WAR-CR2-06.40, BUTLER WARREN AT PRINCETON ROAD IMPROVEMENTS

Contract 2022-03 - Schedule of Prices

Report Date: 03/16/2022

Line	Number	Description	Unit	Quantity	Unit Price	Total
28	878E25000	INSPECTION AND COMPACTION TESTING OF UNBOUND MATERIALS	LS	1		
TOTAL: EROSION CONTROL						
03-DRAINAGE						
29	602E20000	CONCRETE MASONRY Headwalls	CY	2		
30	605E11100	6" SHALLOW PIPE UNDERDRAINS	FT	2,310		
31	605E31100	AGGREGATE DRAINS	FT	700		
32	BC811E00406	4" CONDUIT, TYPE F Contingency Item Only	FT	100		
33	BC811E01500	6" CONDUIT, TYPE F	FT	90		
34	BC811E981501	CATCH BASIN NO. 3	EA	1		
35	BC811E98180	CATCH BASIN 3A	EA	2		
36	BC811E98450	CATCH BASIN 2-2A	EA	1		
37	BC811E046001	12" CONDUIT, TYPE C - 707.33	FT	263		
38	BC811E07400	18" CONDUIT, TYPE B - 707.33	FT	260		
39	BC811E16200	36" CONDUIT, TYPE A 706.02 OR 707.69	FT	50		
40	BC811E99710	PRECAST REINFORCED CONCRETE OUTLET	EA	3		
41	BC811E044001	12" CONDUIT, TYPE B - 707.33	FT	36		
TOTAL: DRAINAGE						
04-PAVEMENT						
42	253E01000	PAVEMENT REPAIR	SY	363		
43	254E01000	PAVEMENT PLANING, ASPHALT CONCRETE 1.5"	SY	1,740		
44	254E01001	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN 1.5" - 3"	SY	5,505		
45	301E46000	ASPHALT CONCRETE BASE, PG64-22	CY	2,550		
46	301E48000	ASPHALT CONCRETE BASE, PG64-22 (DRIVEWAYS)	CY	10		
47	301E46001	ASPHALT CONCRETE BASE, PG64-22, AS PER PLAN	CY	148		
48	304E20000	AGGREGATE BASE	CY	1,804		
49	407E20000	NON-TRACKING TACK COAT	GAL	1,083		
50	408E10000	PRIME COAT	GAL	6,687		
51	441E50101	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), AS PER PLAN	CY	700		
53	441E50400	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), (DRIVEWAYS)	CY	14		
54	452E12010	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	SY	201		
55	608E52001	CURB RAMP, AS PER PLAN	SF	152		

WAR-CR2-06.40, BUTLER WARREN AT PRINCETON ROAD IMPROVEMENTS

Contract 2022-03 - Schedule of Prices

Report Date: 03/16/2022

Line	Number	Description	Unit	Quantity	Unit Price	Total
56	608E53020	DETECTABLE WARNING	SF	16		
57	609E26000	CURB, TYPE 6	FT	328		
98	452E10010	6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	SY	73		
100	441E50301	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448), AS PER PLAN Variable Depth, 1.5"-4.5"	CY	155		
103	441E50300	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)	CY	700		
					TOTAL: PAVEMENT	
05-WATER WORK						
58	638E02400	12" WATER MAIN DUCTILE IRON PIPE ANSI CLASS 52, PUSH-ON JOINTS AND FITTINGS	FT	377		
59	638E00700	6" WATER MAIN DUCTILE IRON PIPE ANSI CLASS 52, MECHANICAL JOINTS AND FITTINGS	FT	50		
60	638E04800	3/4" COPPER SERVICE BRANCH	FT	71		
61	638E08710	12" CUTTING-IN SLEEVE connect to existing watermain, include thrust block	EACH	2		
62	638E07500	12" GATE VALVE	EACH	2		
63	638E10200	6" FIRE HYDRANT	EACH	1		
64	638E10500	FIRE HYDRANT REMOVED AND RESET	EACH	1		
65	638E10600	FIRE HYDRANT AND GATE VALVE REMOVED AND RESET	EACH	4		
					TOTAL: WATER WORK	
06-SANITARY SEWER						
66	BC811E02000	8" CONDUIT, TYPE C DI, CL53, San. Force Main	FT	288		
67	BC811E97200	CONDUIT MISC.: Connect to Existing 8" Force Main	EACH	1		
68	BC811E99690	MANHOLE, MISC Connect to Existing Sanitary MH	EA	1		
69	BC811E99574	MANHOLE, NO 3	EA	1		
99	BC811E02000A	8" CONDUIT, TYPE C PVC SDR35	FT	286		
					TOTAL: SANITARY SEWER	
07-TRAFFIC CONTROL						
70	621E00100	RPM	EACH	86		
71	630E85100	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	EACH	1		
72	630E84900	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	EACH	13		
73	630E80100	SIGN, FLAT SHEET	SF	117		
74	630E03100	GROUND MOUNTED SUPPORT, NO. 3 POST	FT	263		
75	644E00300	CENTER LINE	MILE	0.97		
76	644E00100	EDGE LINE, 4"	MILE	1.3		

WAR-CR2-06.40, BUTLER WARREN AT PRINCETON ROAD IMPROVEMENTS

Contract 2022-03 - Schedule of Prices

Report Date: 03/16/2022

Line	Number	Description	Unit	Quantity	Unit Price	Total
77	644E00700	TRANSVERSE/DIAGONAL LINE	FT	140		
78	644E00400	CHANNELIZING LINE, 8"	FT	1,800		
79	644E00900	ISLAND MARKING	SF	60		
81	644E00500	STOP LINE 24"	FT	110		
82	644E01300	LANE ARROW	EACH	32		
94	630E86002	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	EACH	12		
					TOTAL: TRAFFIC CONTROL	
08-INCIDENTALS						
83	614E11000	MAINTAINING TRAFFIC	LS	1		
84	615E20000	PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A	SY	477		
85	616E10000	WATER	MGAL	6		
86	623E10000	CONSTRUCTION LAYOUT STAKES AND SURVEYING	LS	1		
87	624E10000	MOBILIZATION	LS	1		
95	802E00001	PREMIUM ON INDUSTRIAL INSURANCE	LS	1		
96	802E00002	PREMIUM ON BID BOND	LS	1		
97	802E00003	CONTINGENCIES The Contractor shall enter \$1.00 in the unit price column and \$220,000.00 in the total column. If the Contractor neglects to enter the correct figure(s), the Contractor's bid will be corrected and the process for "Mistake in Bid" shall follow. This item will be used in the event that there are change orders in the Contract. No work will be paid or recognized under this item unless agreed upon in writing by an authorized representative of the Butler County Engineer's Office.	EA	220,000		
102	615E10000	ROADS FOR MAINTAINING TRAFFIC	LS	1		
					TOTAL: INCIDENTALS	
09-ALTERNATE #1						
88	204E10000	SUBGRADE COMPACTION	SY	335		
89	BC811E984701	CATCH BASIN NO. 2-2B	EA	1		
90	BC811E046001	12" CONDUIT, TYPE C	FT	29		
91	BC811E98690	CATCH BASIN, MISC: Connect to Existing Catch Basin	EA	1		
92	304E20000	AGGREGATE BASE	CY	37		
93	608E12000	5" CONCRETE WALK	SF	3,021		
					TOTAL: ALTERNATE #1	

WAR-CR2-06.40, BUTLER WARREN AT PRINCETON ROAD IMPROVEMENTS							
Contract 2022-03 - Schedule of Prices							
Report Date: 03/16/2022							
Line	Number	Description	Unit	Quantity	Unit Price	Total	
						TOTAL: BASE BID	
						TOTAL: BASE BID / ALTERNATE #1	