

ADDENDUM #4						
Contract CR20-04.973, Tylersville Road Traffic Signal - Schedule of Prices						
Report Date: 7/6/2022						
Line	Number	Description	Unit	Quantity	Unit Price	Total
<b>01-ROADWAY</b>						
1	201E11000	CLEARING AND GRUBBING	LS	1		
2	202E30000	WALK REMOVED	SF	598		
3	202E32500	CURB AND GUTTER REMOVED	FT	75		
4	202E23000	PAVEMENT REMOVED	SY	10		
5	202E98100	REMOVAL MISC.: Landscape Rock	EACH	2		
6	608E12000	5" CONCRETE WALK	SF	587		
7	608E52000	CURB RAMP	SF	396		
8	609E12001	COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN BCEO Standard C-1	FT	75		
						TOTAL: ROADWAY
<b>02-EROSION CONTROL</b>						
9	659E00300	TOPSOIL	CY	17		
10	659E10001	SEEDING AND MULCHING, AS PER PLAN	SY	145		
11	659E20000	COMMERCIAL FERTILIZER	TON	0.02		
12	659E35000	WATER	MGAL	1		
13	832E30000	EROSION CONTROL This item is for the installation of Storm Water BMPS as defined in appendix "F" of ODOT supplemental specifications 832. The Contractor shall enter \$1.00 in the unit price column and \$1000.00 in the total column. If the Contractor neglects to enter the correct figure(s) the Contractors bid will be corrected and the process for "Mistake In Bid" shall follow. No work will be recognized or paid under this item unless agreed upon and approved by an authorized representative of the Butler County Engineer's Office.	EACH	1,000		
						TOTAL: EROSION CONTROL
<b>03-PAVEMENT</b>						
14	204E10000	SUBGRADE COMPACTION	SY	83		
15	301E46000	ASPHALT CONCRETE BASE, PG64-22	CY	3		
16	304E20000	AGGREGATE BASE	CY	6		
17	441E50000	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	CY	1		
						TOTAL: PAVEMENT
<b>04-TRAFFIC CONTROL</b>						
18	630E03100	GROUND MOUNTED SUPPORT, NO. 3 POST	FT	28		

ADDENDUM #4						
Contract CR20-04.973, Tylersville Road Traffic Signal - Schedule of Prices						
Report Date: 7/6/2022						
Line	Number	Description	Unit	Quantity	Unit Price	Total
19	630E80100	SIGN, FLAT SHEET	SF	18		
20	630E84900	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	EACH	3		
21	630E86002	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	EACH	3		
22	644E00100	EDGE LINE, 4"	MILE	0.01		
23	644E00300	CENTER LINE	MILE	0.01		
24	644E00400	CHANNELIZING LINE, 8"	FT	38		
25	644E00500	STOP LINE	FT	107		
26	644E00600	CROSSWALK LINE	FT	330		
27	644E30000	REMOVAL OF PAVEMENT MARKING	FT	77		
				TOTAL: TRAFFIC CONTROL		
05-MAINTENANCE OF TRAFFIC						
28	614E11110	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	HOURL	20		
73	614E22100	WORK ZONE EDGE LINE, CLASS I, 4", 642 PAINT	MILE	0.01		
74	614E21100	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	MILE	0.01		
75	614E23200	WORK ZONE CHANNELIZING LINE, CLASS I, 8", 642 PAINT	FT	38		
76	614E26200	WORK ZONE STOP LINE, CLASS I, 642 PAINT	FT	107		
77	614E27200	WORK ZONE CROSSWALK LINE, CLASS I, 642 PAINT	FT	330		
				TOTAL: MAINTENANCE OF TRAFFIC		
06-INCIDENTALS						
29	614E11000	MAINTAINING TRAFFIC	LS	1		
30	623E10000	CONSTRUCTION LAYOUT STAKES AND SURVEYING	LS	1		
31	624E10000	MOBILIZATION	LS	1		
32	802E00001	PREMIUM ON INDUSTRIAL INSURANCE	LS	1		
33	802E00002	PREMIUM ON BID BOND	LS	1		
34	802E00003	CONTINGENCIES The Contractor shall enter \$1.00 in the unit price column and \$5,000.00 in the total column. If the Contractor neglects to enter the correct figure(s), the Contractor's bid will be corrected and the process for "Mistake in Bid" shall follow. This item will be used in the event that there are change orders in the Contract. No work will be paid or recognized under this item unless agreed upon in writing by an authorized representative of the Butler County Engineer's Office.	EA	5,000		

ADDENDUM #4						
Contract CR20-04.973, Tylersville Road Traffic Signal - Schedule of Prices						
Report Date: 7/6/2022						
Line	Number	Description	Unit	Quantity	Unit Price	Total
				TOTAL: INCIDENTALS		
07-TRAFFIC SIGNAL						
35	625E00450	CONNECTION, FUSED PULL APART	EACH	4		
36	625E00460	CONNECTION, UNFUSED PULL APART	EACH	4		
37	625E17901	BRACKET ARM, AS PER PLAN	EACH	4		
38	625E23000	NO. 4 AWG 600 VOLT DISTRIBUTION CABLE	FT	450		
39	625E23400	NO. 10 AWG POLE AND BRACKET CABLE	FT	200		
40	625E25304	CONDUIT, 1-1/2", 725.051	FT	125		
41	625E25504	CONDUIT, 3", 725.051	FT	80		
42	625E25906	CONDUIT, JACKED OR DRILLED, 725.051 4"	FT	255		
43	625E26253	LUMINAIRE, CONVENTIONAL, SOLID STATE (LED), AS PER PLAN 120 Volt	EACH	4		
44	625E29000	TRENCH	FT	123		
45	625E30706	PULL BOX, 725.08, 24"	EACH	4		
46	625E32000	GROUND ROD	EACH	6		
47	625E36010	UNDERGROUND WARNING/MARKING TAPE	FT	440		
48	630E79100	SIGN HANGER ASSEMBLY, MAST ARM	EACH	6		
50	630E97700	SIGNING, MISC.: Internally Illuminated Street Name Sign	EACH	3		
51	630E97700C	SIGNING MISC.: Internally Illuminated Fixed Message Sign	EA	3		
52	632E05006	VEHICULAR SIGNAL HEAD, (LED), 3-SECTION, 12" LENS, 1-WAY, POLYCARBONATE	EACH	6		
53	632E05086	VEHICULAR SIGNAL HEAD, (LED), 5-SECTION, 12" LENS, 1-WAY, POLYCARBONATE	EACH	2		
54	632E20731	PEDESTRIAN SIGNAL HEAD (LED), TYPE D2, COUNTDOWN, AS PER PLAN	EACH	8		
55	632E25001	COVERING OF VEHICULAR SIGNAL HEAD, AS PER PLAN	EACH	8		
56	632E25010	COVERING OF PEDESTRIAN SIGNAL HEAD	EACH	8		
57	632E26001	PEDESTRIAN PUSHBUTTON, AS PER PLAN	EACH	4		
58	632E40300	SIGNAL CABLE, 3 CONDUCTOR, NO. 14 AWG	FT	635		
59	632E40700	SIGNAL CABLE, 7 CONDUCTOR, NO. 14 AWG	FT	1,620		
60	632E68300	POWER CABLE, 3 CONDUCTOR, NO. 6 AWG	FT	170		
61	632E70001	POWER SERVICE, AS PER PLAN	EACH	1		



ADDENDUM #4						
Contract CR20-04.973, Tylersville Road Traffic Signal - Schedule of Prices						
Report Date: 7/6/2022						
Line	Number	Description	Unit	Quantity	Unit Price	Total
62	632E70300	CONDUIT RISER, 1-1/2" DIAMETER	EACH	1		
63	632E64011	SIGNAL SUPPORT FOUNDATION, AS PER PLAN	EACH	4		
64	632E80700	SIGNAL SUPPORT, MISC.: Combination Signal Pole, Type TC-81.22, Design 4	EACH	2		
65	632E80700A	SIGNAL SUPPORT, MISC.: Combination Signal Pole, Type TC-81.22, Design 12	EA	2		
66	633E67101	CABINET FOUNDATION, AS PER PLAN	EACH	1		
67	633E67201	CONTROLLER WORK PAD, AS PER PLAN	EACH	1		
68	633E75001	UNINTERRUPTIBLE POWER SUPPLY (UPS), 1000 WATT, AS PER PLAN	EACH	1		
69	633E99000A	CONTROLLER ITEM, MISC.: Controller Unit, TS2/A2, with Cabinet, Typer TS I, As Per Plan	EA	1		
70	633E99000B	CONTROLLER ITEM, MISC.: Emergency Vehicle Preemption	EA	1		
71	809E69001	ADVANCE RADAR DETECTION, AS PER PLAN	EACH	2		
78	809E69101	STOP LINE RADAR DETECTION, AS PER PLAN	EACH	4		
					TOTAL: TRAFFIC SIGNAL	
					TOTAL BID:	