

## July 7th, 2022

## Greenlawn Road Drainage Improvements Phase A Contract 2022-13

## Addendum No. 1

**Add Note: Coordination with Duke Gas** – Existing gas main will need to be cut & capped by Duke Gas to allow installation of the 60" storm sewer at 13+50L. Contractor is to remove concrete and blacktop 15' in each direction of the proposed storm sewer over the existing gas main. Once removal is complete, notify Mark Conner, Utility Coordinator, Butler County Engineer's Office (513-291-7463). Duke Gas will then need one full week to schedule crews and two days onsite to cut & cap the existing gas main. Once the gas main is capped, the contractor must install the 60" storm sewer prior to September 23, 2022. Notify Mark Conner once 60" storm sewer is completed and allow Duke one full week to schedule crews and two days onsite to reinstall the gas main over the storm sewer. All cost associated with this work is considered incidental to the contract.

Right of Way is Clear.