

ITEM	GRAND TOTAL	UNIT	DESCRIPTION
201E11000	LUMP	LS	CLEARING AND GRUBBING
202E11000	LUMP	LS	STRUCTURE REMOVED, CORRUGATED METAL PIPE ARCH WITH HEADWALLS
202E98000	LUMP	LS	REMOVAL MISC: CONCRETE BLOCKS
202E75000	282	FT	FENCE REMOVED
203E20000	280	CY	EMBANKMENT
203E10000	350	CY	EXCAVATION
301E56000	16	CY	ASPHALT CONCRETE BASE, PG64-22
407E10000	5	GAL	TACK COAT
441E50000	4	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22
441E50200	4	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448)
451E20000	14	SY	REINFORCED CONCRETE PAVEMENT, MISC: AS PER PLAN
503E21100	LUMP	LS	UNCLASSIFIED EXCAVATION (WINGWALLS & FOOTINGS)
503E11100	LUMP	LS	COFFERDAMS AND EXCAVATION BRACING
509E10000	2346	LBS	EPOXY COATED REINFORCING
511E46010	6	CY	CLASS QCI CONCRETE, RETAINING/WINGWALL NOT INCLUDING FOOTING
511E46510	19	CY	CLASS QCI CONCRETE, FOOTING
511E46610	1	CY	CLASS QCI CONCRETE, HEADWALL
512E33001	64	SY	TYPE 2 WATERPROOFING, AS PER PLAN
512E33010	81	SY	TYPE 3 WATERPROOFING
512E10100	27	SY	SEALING OF CONCRETE SURFACES (EPOXY - URETHANE)
516E13600	20	SF	1" PREFORMED EXPANSION JOINT FILLER
518E21050	LUMP	LS	POROUS BACKFILL WITH GEOTEXTILE FABRIC
601E34200	4	CY	ROCK CHANNEL PROTECTION, TYPE C, WITHOUT FILTER
601E35000	LUMP	LS	ROCK CHANNEL PROTECTION MISC: AS PER PLAN
614E11000	LUMP	LS	MAINTAINING TRAFFIC
616E10000	2	MGAL	WATER
623E10000	LUMP	LS	CONSTRUCTION LAYOUT STAKES AND SURVEYING
624E10000	LUMP	LS	MOBILIZATION
642E00100	0.01	MILE	EDGE LINE, 4"
642E00300	0.01	MILE	CENTER LINE, DOUBLE YELLOW
659E10001	2603	SY	SEEDING AND MULCHING, AS PER PLAN
659E20000	0.23	TON	COMMERCIAL FERTILIZER
659E35000	14	MGAL	WATER
670E00520	1130	SY	SLOPE EROSION PROTECTION MAT, TYPE B
671E15010	247	SY	EROSION CONTROL MAT, TYPE B
BC 811	64	FT	8' x 3', TYPE A, PRECAST REINFORCED CONCRETE BOX SECTIONS, 706.05
832E30000	15000	EACH	EROSION CONTROL
832E15000	LUMP	LS	STORM WATER POLLUTION PREVENTION PLAN
832E15002	LUMP	LS	STORM WATER POLLUTION PREVENTION INSPECTIONS

CALCULATED
MG
CHECKED
KVS

GENERAL SUMMARY

BUT - CR216 - 04.245