



**November 3, 2022**

**Contract 2023-01  
2023 Structures (Gene Ave, Gates Rd, Chapel Rd)**

**Addendum #3**

**ADD PROPOSAL NOTE: "General and Sub Contractor Qualifications"**

**Description:** This item shall consist of the General Contractor and all Subcontractors providing work on the project being in good standing on the Ohio Department of Transportation's approved contractor listing for the type of construction required by the project with this exception; Landscape Subcontractors. The Contractor must submit a certification of qualifications showing they are a pre-qualified contractor registered through Ohio Department of Transportation for the type of work that they will be performing. **NONCOMPLIANCE WILL VOID THE CONTRACTORS BID.**

Landscape Subcontractors not on the ODOT prequalified list must submit written proof of successfully performing the type of work of which they will be performing on this project on a minimum of three recent ODOT projects and are strictly limited to performing the following;

- Item 652, Placing Stockpiled Topsoil
- Item 653, Topsoil Furnished and Placed
- Item 654, Renovating Existing Soil
- Item 657, Riprap for Tree Protection
- Item 658, Tree Root Aeration
- Item 659, Seeding and Mulching
- Item 660, Sodding
- Item 661, Planting Tree, Shrubs, Perennials and Vines
- Item 662, Landscape Watering
- Item 666, Pruning Existing Trees
- Item 670, Erosion Protection
- Item 671, Erosion Control Mats
- SS 832, Construction Seeding and Mulching
- SS 832, Perimeter Filter Fabric Fence
- SS 832, Filter Fabric Ditch Check
- SS 832, Inlet Protection
- SS 832, Construction Ditch Protection
- SS 832, Construction Mulching
- SS 832, Winter Seeding and Mulching

The Butler County Engineer reserves the right to reject any subcontracting landscaper who in the opinion of the Engineer has not successfully performed Work on any Butler County project.

**ADD PROPOSAL NOTE: "Precast Concrete for Gene Ave and Chapel Rd"**

At the option of the contractor, precast headwalls and wingwalls may be furnished per item 602. 03 precast structures, provided they are sized to meet the soil loading and resistance parameters, and meet or exceed the material strengths and wall limits as shown and specified. All drawings and calculations shall be stamped by an engineer registered in the State of Ohio and shall be submitted for review. Full compensation for the precast substitution is the volume of concrete and the weight of the reinforcing steel for the corresponding cast -in -place structure.

**ADD PROPOSAL NOTE: "Precast Concrete for Gates Rd"**

At the option of the contractor, precast headwalls and wingwalls may be furnished per item 602. 03 precast structures, provided they are sized to meet the soil loading and resistance parameters, and meet or exceed the material strengths and wall limits as shown and specified. All drawings and calculations shall be stamped by an engineer registered in the State of Ohio and shall be submitted for review. Full compensation for the precast headwalls and wingwalls shall be paid per BC811 Type A Precast Reinforced Concrete Culvert, APP.

**Please e-mail or call our office when you have received this Addendum.**

**[taylor@mceo.org](mailto:taylor@mceo.org)**

**Melissa Taylor; 513-785-4115**