



**December 8, 2022**

**Contract 2022-24  
Cured In Place Pipe Repair of Various Storm Sewer Phase 3  
Addendum #4**

**Delete Proposal Note: Special**                    ***“Contract Time Line”***

**Description:** This project will have a completion date of **June 1, 2023** with liquidated damages set in specification 108.07.

**Construction start date: January 1, 2023**

**Contract completion: June 1, 2023**

**Add Proposal Note: Special**                    ***“Contract Time Line”***

**Description:** This project will have a completion date of **June 1, 2023** with liquidated damages set in specification 108.07.

**Construction start date: January 1, 2023**

**Contract completion: August 1, 2023**

**Delete Proposal Note: Special:**                    ***“Manholes and Catch Basins”***

At the direction of the Engineer the Contractor may remove portions of existing manholes, catch basins and curbs to access the work. No manhole, catch basin and curb shall be removed without prior approval from the Engineer. Removal and installation of existing curb, manholes and catch basins is considered incidental to the associated pipe lining item.

- No excavation or removal shall be left unprotected from the traveling public or pedestrians at any time.
- Restoration and backfill of the excavation or removal shall proceed in a timely manner.
- All removed portions of manholes or catch basins are to be reused, unless it is found that the item is in

such disrepair and cannot be reconstructed through normal operations. If this is found contractor shall immediately notify the Engineer.

- Any and all conduit connections to existing manholes or catch basins must be restored in kind or better.
- If necessary to remove portions of catch basins to perform the Work the adjoining curb removal shall be limited to the nearest control joint in the curb line.
- Any required removal and replacement of existing pavement and curb & gutter is incidental to all Contract Items and shall be as per ODOT CMS Sections 202, 203, 253, 254 and Butler County Standard Drawing C16, CURB AND GUTTER STANDARD C-1
- Existing head walls and outlet structures shall not be damaged or removed without prior permission from the Engineer

**Add Proposal Note: Special:**                    *“Manholes and Catch Basins”*

At the direction of the Engineer the Contractor may remove portions of existing manholes, catch basins and curbs to access the work. No manhole, catch basin and curb shall be removed without prior approval from the Engineer. Removal and installation of existing curb, manholes and catch basins is considered incidental to the associated pipe lining item.

- No excavation or removal shall be left unprotected from the traveling public or pedestrians at any time.
- Restoration and backfill of the excavation or removal shall proceed in a timely manner.
- **All removed portions of manholes or catch basins are to be reused or replaced with new.**
- Any and all conduit connections to existing manholes or catch basins must be restored in kind or better.
- If necessary to remove portions of catch basins to perform the Work the adjoining curb removal shall be limited to the nearest control joint in the curb line.
- Any required removal and replacement of existing pavement and curb & gutter is incidental to all Contract Items and shall be as per ODOT CMS Sections 202, 203, 253, 254 and Butler County Standard Drawing C16, CURB AND GUTTER STANDARD C-1
- Existing head walls and outlet structures shall not be damaged or removed without prior permission from the Engineer.

**Clarifications:**

Q1: Will you accept a UV cured, glass reinforced CIPP as an acceptable alternate to felt for this project?

A1: No.

Q2: Is there any heavy cleaning allowed on this or is all cleaning, regardless of regular/light and heavy all pricing out in the cleaning item?

A2: Cleaning bid item shall cover light cleaning and heavy cleaning.

**Please e-mail or call our office when you have received this Addendum.  
taylor@mceo.org  
Melissa Taylor; 513-785-4115**