

CRESCENTVILLE ROAD STORM WATER STRUCTURE SUB-SUMMARY

AGENCY	BCEO GIS OBJECT ID	FIELD IDENTIFICATION NUMBER	CATCH BASIN TYPE	202 CURB REMOVED AT CATCH BASINS, APP	609 COMBINATION CURB AND GUTTER, TYPE 2 AS PER PLAN	202 CATCH BASIN REMOVED	BC811 CATCH BASIN, NO. 3, DOUBLE GRATE	BC811 CATCH BASIN, NO. 3A	BC811 CATCH BASIN, NO. 3A, AS PER PLAN, SINGLE GRATE	BC611E98181A CATCH BASIN, NO. 3A, (MODIFIED), APP CLEAN AND PLASTER	BC811 CATCH BASIN, NO. 2-2B, APP, CLEAN AND PLASTER	BC811 CATCH BASIN, NO. 3A, AS PER PLAN, (MODIFIED)	BC811 CATCH BASIN NO 3 RECONSTRUCTED TO GRADE, AS PER PLAN	BC811 CATCH BASIN NO 3A RECONSTRUCTED TO GRADE, AS PER PLAN	BC811 12" CONDUIT, TYPE C, AS PER PLAN, CONTINGENCY	BC811 15" CONDUIT, TYPE C, AS PER PLAN, CONTINGENCY	BC811 24" CONDUIT, TYPE C, AS PER PLAN, CONTINGENCY	BC811 CATCH BASIN, NO. 2-2B RECONSTRUCTED AS PER PLAN	LONG DESCRIPTION
				FT	FT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	FT	FT	FT	EACH	
SPRINGDALE	19103	103R	CB 3A SINGLE GRATE	10	10	1			1						10				TOTAL REMOVAL AND REPLACEMENT, (SHALLOW)
SPRINGDALE	19105	105R	CB 3 DOUBLE GRATE	10	10	1	1										10		TOTAL REMOVAL AND REPLACEMENT, (SHALLOW)
SPRINGDALE	19109	109R	CB 3A MOD / CB-3	10	10	1	1								5				TOTAL REMOVAL AND REPLACEMENT, (SHALLOW)
SPRINGDALE	19110	110R	CB 3A	10	10	1		1								5			TOTAL REMOVAL AND REPLACEMENT, (SHALLOW)
SPRINGDALE	19112	112R	CB 3A SINGLE GRATE	10	10	1			1						5				TOTAL REMOVAL AND REPLACEMENT, (SHALLOW)
SPRINGDALE	19127	127R	CB 3A	10	10	1		1							5				TOTAL REMOVAL AND REPLACEMENT, (SHALLOW)
SPRINGDALE	19128	128R	CB 3A	10	10	1		1							5				TOTAL REMOVAL AND REPLACEMENT, (SHALLOW)
SPRINGDALE	19132	132R	CB 3A MOD / CB-3	10	10	1	1									5			TOTAL REMOVAL AND REPLACEMENT,(DEEP)
SPRINGDALE	19135	135R	CB 3A	10	10	1		1							5				TOTAL REMOVAL AND REPLACEMENT,(DEEP)
SPRINGDALE	19139	139R	CB 3A	10	10	1		1							5				TOTAL REMOVAL AND REPLACEMENT,(DEEP)
SPRINGDALE	19140	140R	CB 3A	10	10	1		1							5	5			TOTAL REMOVAL AND REPLACEMENT,(DEEP)
SPRINGDALE	19156	156R	CB 3A	10	10	1		1								5			TOTAL REMOVAL AND REPLACEMENT, (SHALLOW)
SPRINGDALE	19114	114R	CB 3A	10	10									1					CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
SPRINGDALE	19115	115R	CB 3	10	10								1						CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
SPRINGDALE	19119	119R	CB 3A	10	10									1					CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
SPRINGDALE	19121	121R	CB 3	10	10								1						CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
SPRINGDALE	19125	125R	CB 3A	10	10									1					CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
SPRINGDALE	19137	137R	CB 3A	10	10									1					CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
SPRINGDALE	19141	141R	CB 3A	10	10									1					CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS

SPRINGDALE	19152	152R	CB 3A	10	10													CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
SPRINGDALE	19154	154R	CB 3	10	10							1						CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
SPRINGDALE	19157	157R	CB 3A	10	10													CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
SPRINGDALE	19161	161R	CB 3	10	10							1						CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
SPRINGDALE	16417	417R	CB 3A	10	10													CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
SPRINGDALE	19736	736R	CB 3A	10	10													CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
SPRINGDALE TOTALS				250	250	12	3	7	2	0	0	0	4	9	45	20	10	0

AGENCY	BCEO GIS OBJECT ID	FIELD IDENTIFICATION NUMBER	CATCH BASIN TYPE	202 CURB REMOVED AT CATCH BASINS, APP	609 COMBINATION CURB AND GUTTER, TYPE 2 AS PER PLAN, AT CATCH BASINS	202 CATCH BASIN REMOVED	611 CATCH BASIN, NO. 3	611 CATCH BASIN, NO. 3A	611 CATCH BASIN, NO. 3A, AS PER PLAN, SINGLE GRATE	BC611E98181A CATCH BASIN, NO. 3A, (MODIFIED), APP CLEAN AND PLASTER	611 CATCH BASIN, NO. 2-2B, APP, CLEAN AND PLASTER	611 CATCH BASIN, NO. 3A, AS PER PLAN, (MODIFIED)	BC811 CATCH BASIN NO 3 RECONSTRUCTED TO GRADE, AS PER PLAN	BC811 CATCH BASIN NO 3A RECONSTRUCTED TO GRADE, AS PER PLAN	12" CONDUIT, TYPE C, AS PER PLAN, CONTINGENCY	15" CONDUIT, TYPE C, AS PER PLAN, CONTINGENCY	24" CONDUIT, TYPE C, AS PER PLAN, CONTINGENCY	BC811 CATCH BASIN, NO. 2-2B RECONSTRUCTED AS PER PLAN	LONG DESCRIPTION
				FT	FT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	FT	FT	FT	EACH	
BUTLER	19113	113L	CB 3A	10	10	1		1								5	10		TOTAL REMOVAL AND REPLACEMENT, (SHALLOW)
BUTLER	19116	116L	CB 3	10	10	1	1								5	5			TOTAL REMOVAL AND REPLACEMENT, (SHALLOW)
BUTLER	19102	102L	CB 3A SINGLE GRATE	10	10	1			1						5	5			TOTAL REMOVAL AND REPLACEMENT, (SHALLOW)
BUTLER	19111	111L	CB 3A SINGLE GRATE	10	10									1					CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
BUTLER	19118	118L	CB 3A	10	10									1					CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
BUTLER	19124	124L	CB 3A	10	10									1					CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS
BUTLER	19131	131L	CB 3A	10	10									1					CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS

BUTLER	19107	107L	CB 2-2B														1	CB REPAIR, CLEAN CB, REPLACE TOP AND USE RISERS TO ADJUST TO GRADE, (1 +/- FT RISER), PLASTER CB WALLS	
BUTLER COUNTY TOTALS				70	70	3	1	1	1	0	0	0	0	4	10	15	10	1	

CONTRACT TOTALS				320	320	15	4	8	3	0	0	0	4	13	55	35	20	1	
-----------------	--	--	--	-----	-----	----	---	---	---	---	---	---	---	----	----	----	----	---	--